

QUIZ NO: 386

TOPIC: ESTIMATON

DATE: 05/01/2021

1. The damp proof course is measured in

[1] Sq.m

[2] Cu.m

[3] Metre

[4] Kg

Answer: A

2. The ratio of cost of labour to the cost of the building is

[1]1:1

[2]1:10

[3]1:10

[4]1:4

Answer: D

3. The expected out turn for excavation in rock per mazdoor per day is

[1] 1m^3

[2] 2m^3

[3] 3m^3

[4] 4m^3

Answer: A

4. The number of standard brick required for 15m^3 of brick work in cm 1:6 is

[1] 750

[2] 7500

[3] 900

[4] 9000

Answer: B

5. Due to change in price level, a revised estimate is prepared if the sanctioned estimate exceeds

[1] 2 %

[2] 3 %

[3] 4 %

[4] 5 %

Answer: D

6. The item not included in the plinth area is

- [1] Toilet Area
- [2] Courtyard Area
- [3] Veranda area
- [4] Wall thickness

Answer: B

7. The estimate which prepared for technical sanction of an authority is

- [1] Plinth area Estimate
- [2] Rough Cost Estimate
- [3] Detailed Estimate
- [4] Cube Rate Estimate

Answer: C

8. A preliminary estimate of a building is prepare by

- [1] Approximate quantity method basis
- [2] Cube content basis
- [3] Plinth area basis
- [4] All of the above

Answer: D

9. Which department looks after the execution and maintenance of water supply and sanitary works?

- [1] Central Ground Water board
- [2] Public Health Department
- [3] Social Welfare Department
- [4] None of these

Answer: B

10. Valuation of a property is usually done for

- [1] Taxation
- [2] Rent fixation
- [3] Insurance
- [4] Any of the above

Answer: D

Join our social media platforms

