

QUIZ NO: 453

TOPIC: ESTIMATION

DATE: 11/06/2021

1. Which of the following, is not an approximate estimate

- [A] Cube rate estimate
- [B] Unit rate estimate
- [C] Supplementary estimate
- [D] Plinth area estimate

Answer: C

2. The initial lead (or- normal lead) distance, in earthwork estimation is employed is

- [A] 10 m
- [B] 50 m
- [C] 25 m
- [D] 15 m

Answer: B

3. The out- turn of a mason/day, in Brickwork using cement motor in super structure, as per standards, should be

- [A] 1.75 m³
- [B] 1.50 m³
- [C] 1.24 m³
- [D] 1.00 m³

Answer: D

4. The weight of 1 m³ of Portland cement is

- [A] 1440 kg
- [B] 1500 kg
- [C] 1560 kg
- [D] 1620 kg

Answer: A

5. The amount to be spent for the completion of unit quantity of a particular work, is termed as

- [A] Cost
- [B] Rate
- [C] Estimate
- [D] Expense

Answer: B

6. In the analyses of rates, the provision included, as contractor's profit is

- [A] 4%
- [B] 6%
- [C] 8%
- [D] 10%

Answer: D

7. In painting of doors, the multiplying factor, for each side, of a 'paneled door 'is

- [A] 0.50
- [B] 1.00
- [C] 1.125
- [D] 1.25

Answer: C

8. When small items, are estimated, for which detailed quantities cannot be taken out, they are considered as

- [A] Lump sum
- [B] Sundries
- [C] Contingencies
- [D] None of these

Answer: A

9. In public building the maximum riser is limited to

- [A] 10 cm
- [B] 15 cm
- [C] 18 cm
- [D] 30 cm

Answer: B

10. In residential building, the width of a door should not be less than

- [A] 102 cm
- [B] 1 cm
- [C] 80 cm
- [D] 75 cm

Answer: D

Join our social media platforms

