



9497498415 | 16 | 17

ANSWER KEY

**QUIZ NO: 790** 

**TOPIC: ESTIMATION** 

DATE: 02/01/2024

- 1. A work costing Rs. 20000 is termed as
  - [A] Petty work
  - [B] Minor work
  - [C] Major work
  - [D] Minor project

Answer: A

- 2. Specifications for the holdfast are given in terms of:
  - [A] Number
  - [B] Weight
  - [C] Volume
  - [D] Length

**Answer: B** 





## 9497498415

ANSWER KEY

Э.	The measurement not made in 5q.m
	[A] Damp proof course
	[B] Form works
	[C] Concrete jaffries
	[D] R.C Chhajja
	Answer: D
4.	What is the approximate cost of the complete labour as a percentage of the total cost of the building?
	[A] 0.1
	[B] 0.25
	[C] 0.4
	[D] 0.05
	Answer: B
5.	To make out an estimate for a work the following data are necessary-Drawing, Specification and
	[A] Materials
	[B] Rates
	[C] Labours
	[D] Transportation
	Answer: B





## 9497498415 | 16 | 17

ANSWER KEY

6.	A large work or project may consists of several building or small works and each of these work is known as
	[A] Sub-work
	[B] Sub-project
	[C] Sub-head
	[D] Sub-construction
	Answer: A
7	. The expected out turn of cement concrete 1:2:4 per mason per day is
	[A] 1.5 m <sup>3</sup>
	[B] 2.5 m <sup>3</sup>
	[C] 3.5 m <sup>3</sup>
	[D] 5.0 m <sup>3</sup>
	Answer: D
8	3. The head of the division of public works department is
	[A] Chief engineer
	[B] Superintending engineer
	[C] Executive engineer
	[D] Over bridge
	Answer: C





## 9497498415 | 16 | 17

ANSWER KEY

- 9. When small items are estimated, for which detailed quantities cannot be taken out, they are considered as:
  - [A] Lump sum
  - [B] Contingencies
  - [C] Sundries
  - [D] None of these

**Answer: A** 

- 10. Normally earthwork is estimated for 30 m lead for distance and 1.5 m lift for height or depth, and this distance of 30 m and the height of 1.5 m are known as
  - [A] Vertical lead and lift
  - [B] Normal lead and lift
  - [C] Horizontal lead and lift
  - [D] Transverse lead and lift

**Answer: B** 

Join our social media platforms









